

ATHLETICS COMPLEX IMPROVEMENTS AT JARRELL HIGH SCHOOL FOR JARRELL I.S.D. JARRELL, TEXAS

**High School Stormwater Project
Detention and Water Quality Pond**

PACKAGE 1 - CIVIL

10/28/2021 4:07:38 PM
BIN:390-JARRELL ISD - ATHLETICS & STADIUM IMPROVEMENTS183646-01_JarrellISD_MS-Architectural_ARC01_V16.rvt

Copyright © 2021, Huckabee & Associates, Inc.

Date


Revision /

Project:
ATHLETICS COMPLEX IMPROVEMENTS
AT JARRELL HIGH SCHOOL
FOR
JARRELL I.S.D.
1100 FM 487, JARRELL, TEXAS 76537



COVER SHEET

PACKAGE 1	
Job No. 1836-06-01	Sheet No.
Drawn By: JMA	G1.01
Date: 10/28/2021	



Drainage Area Designation	Drainage Area (ac)	Runoff Coefficient "C"				Time of Concentration (min)	2-Year Rainfall Intensity (I2)		10-Year Rainfall Intensity (I10)		25-Year Rainfall Intensity (I25)		100-Year Rainfall Intensity (I100)		Comments
		2-YR	25-YR	100-YR	100-YR		(in/hr)	(in/hr)	(in/hr)	(in/hr)	(in/hr)	(in/hr)	(in/hr)	(in/hr)	
		0.35	0.38	0.44	0.51		49	1.97	45.53	3.92	73.68	3.68	105.85	4.88	
DA-1	65.17	0.35	0.38	0.44	0.51	49	1.97	45.53	3.92	73.68	3.68	105.85	4.88	183.57	Bypass pond
DA-2	49.83	0.46	0.50	0.56	0.64	30	2.89	61.67	4.07	101.92	4.89	136.53	6.43	203.36	Overflow and pipe to ex. pond
DA-2A†	10.14	0.48	0.53	0.58	0.66	31	2.63	72.83	3.99	21.32	4.60	28.42	6.31	42.25	Overflow and pipe to Pond 4
DA-3	40.06	0.40	0.44	0.50	0.57	30	2.69	43.31	4.07	71.83	4.89	97.57	6.43	146.81	To Pond 2
DA-3A†	14.40	0.36	0.39	0.45	0.52	19	3.56	18.43	5.34	30.08	6.39	41.47	8.27	62.06	Overflow and pipe to Pond 2
DA-4	0.24	0.75	0.83	0.88	0.97	10	4.62	0.83	6.89	1.38	8.19	1.74	10.40	2.43	To Pond 1
DA-5	6.18	0.55	0.60	0.65	0.73	20	3.37	11.36	5.07	18.78	6.07	24.56	7.88	35.77	To Pond 4
DA-6	0.62	0.75	0.83	0.88	0.97	10	4.62	1.82	6.89	3.00	8.19	3.78	10.40	5.29	To Pond 3
DA-7	0.67	0.75	0.83	0.88	0.97	10	4.62	2.32	6.89	3.84	8.19	4.83	10.40	6.76	To Pond 1
TOTAL	162.49							166.64		276.13		374.85		662.99	

† These areas are subcatchments to show flow to key points. These areas are not subtracted from the parent catchments.

**** NOTICE TO CONTRACTORS - TOPOGRAPHIC SURVEY ****

TOPOGRAPHIC INFORMATION TAKEN FROM A TOPOGRAPHIC SURVEY PERFORMED BY AWARD LAND SURVEYING. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. THE ENGINEER AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY ENGINEER AND OWNER.

****NOTICE TO CONTRACTORS - UTILITIES****

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF ANY EXISTING UTILITIES AS SHOWN ON THESE PLANS ARE BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES, THE GOVERNING MUNICIPALITY, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION PROVIDED IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.



Project: ATHLETICS COMPLEX IMPROVEMENTS AT JARRELL HIGH SCHOOL FOR JARRELL I.S.D. 1100 FM 487, JARRELL, TEXAS 76537

LANGAN | Adams

This drawing was prepared by LANGAN | Adams as an instrument of service and shall remain the property of Langan | Adams. No part of this drawing shall be used for any other project without the written consent of Langan | Adams. The engineer's seal and signature are required for the project to proceed. The engineer's seal and signature are required for the project to proceed. The engineer's seal and signature are required for the project to proceed.

JACK H. GARNER
Professional Engineer
No. 96447
10-28-2021
T&PE Registration #: F-13,709

Huckabee
Austin • Dallas • Fort Worth
Houston • San Antonio • Waco
www.huckabee-inc.com
800.687.0228


COVER SHEET

PACKAGE 1
Job No. 1835-05-01
Sheet No. C3.01
Date: 10/28/2021




Know what's below.
Call before you dig.



THESE PLANS ARE SUBJECT TO REVIEW & APPROVAL BY JURISDICTIONAL ENTITIES.




LEGEND	
DRAINAGE BASIN	DA-00 1.00
DRAINAGE AREA	---
TIME OF CONCENTRATION PATH	---



AREA 1
SCALE: 1" = 40'




AREA 2
SCALE: 1" = 40'



AREA 3
SCALE: 1" = 40'

Drainage Area Designation	Drainage Area (ac)	Runoff Coefficient "C"				Time of Concentration (min)	PRE-DEVELOPMENT DRAINAGE AREA CALCULATIONS									
		2-Yr	10-Yr	25-Yr	100-Yr		2-Year Rainfall Intensity (I ₂) (in/hr)	2-Year Peak Discharge (Q ₂) (cfs)	10-Year Rainfall Intensity (I ₁₀) (in/hr)	10-Year Peak Discharge (Q ₁₀) (cfs)	25-Year Rainfall Intensity (I ₂₅) (in/hr)	25-Year Peak Discharge (Q ₂₅) (cfs)	100-Year Rainfall Intensity (I ₁₀₀) (in/hr)	100-Year Peak Discharge (Q ₁₀₀) (cfs)		
DA-1	11.08	0.42	0.48	0.51	0.59	25	3.31	15.31	4.93	26.30	6.09	34.75	8.05	52.44		
DA-2	6.48	0.33	0.38	0.40	0.46	19	3.74	7.90	5.27	13.60	6.86	17.93	9.05	27.09		
DA-3	1.68	0.45	0.52	0.55	0.63	19	3.78	2.86	5.64	4.88	6.94	6.41	9.15	9.81		
DA-4	1.54	0.47	0.54	0.57	0.65	10	6.08	3.48	7.60	6.27	9.34	8.22	12.29	12.25		
DA-5	2.96	0.36	0.42	0.45	0.52	10	6.02	5.31	7.51	9.27	9.22	12.22	12.14	18.60		
Total	23.74							35.04		60.31		79.51		119.99		

Note: Calculations based on the Rational Method: Q = C*I*A per the 2020 Round Rock Drainage Criteria Manual



AREA 4
SCALE: 1" = 40'

**** NOTICE TO CONTRACTORS - TOPOGRAPHIC SURVEY ****


TOPOGRAPHIC INFORMATION TAKEN FROM A TOPOGRAPHIC SURVEY PERFORMED BY 4WARD LAND SURVEYING. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY IN WRITING OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (P&E), WHICH NEGATIVELY IMPACT THE PROJECT. THE ENGINEER AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY ENGINEER AND OWNER.

****NOTICE TO CONTRACTORS - UTILITIES****

THE CONTRACTOR IS SPECIFICALLY CAUTIONED THAT THE LOCATION AND/OR ELEVATION OF ANY EXISTING UTILITIES AS SHOWN ON THESE PLANS ARE BASED ON RECORDS OF THE VARIOUS UTILITY COMPANIES. THE GOVERNING MUNICIPALITY, AND WHERE POSSIBLE, MEASUREMENTS TAKEN IN THE FIELD. THE INFORMATION PROVIDED IS NOT TO BE RELIED ON AS BEING EXACT OR COMPLETE. THE CONTRACTOR MUST CALL THE APPROPRIATE UTILITY COMPANY AT LEAST 48 HOURS BEFORE ANY EXCAVATION TO REQUEST EXACT FIELD LOCATION OF UTILITIES. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO RELOCATE ALL EXISTING UTILITIES WHICH CONFLICT WITH THE PROPOSED IMPROVEMENTS SHOWN ON THESE PLANS.

Project: ATHLETICS COMPLEX IMPROVEMENTS AT JARRELL HIGH SCHOOL FOR JARRELL I.S.D. 1100 FM 487, JARRELL, TEXAS 76537

LANGAN | Adams



TBPE Registration #: P-13,709



COVER SHEET

PACKAGE 1

Job No. 1836-06-01
Drawn By: [Signature]
Date: 10/28/2021

Sheet No. C3.02

9/14/2021 1:57:27 PM
 C:\Users\jladam\Documents\2018 Revit Local Files\1836-06-01_JarrellISD_HS_AthleticsComplex_ARCH_V19_jladam.rvt


Date
Revision /

ATHLETICS COMPLEX IMPROVEMENTS
AT JARRELL HIGH SCHOOL
FOR
JARRELL I.S.D.
1100 FM 487, JARRELL, TEXAS 76537

Project:

LANGAN | Adams

This drawing was prepared by LANGAN | Adams as an instrument of service, and shall remain the property of LANGAN | Adams. The information herein shall be used only by the client to whom the services are rendered and may be the product of confidential or proprietary information. It shall not be used for any other project or purpose without the express written consent of LANGAN | Adams. The client shall be responsible for obtaining all necessary permits and approvals, including but not limited to, all applicable laws, rules, regulations, and codes. LANGAN | Adams shall not be responsible for any and all liability which may arise from such use.



TBPE Registration #: P-13,709

Huckabee
AUSTIN • DALLAS • FORT WORTH
HOUSTON • SAN ANTONIO • WACO
www.huckabee-inc.com
800.687.0228

WATER QUALITY & DETENTION POND CALCULATIONS

PACKAGE 1 1
Job No. 1835-06-01 Sheet No.
Drawn By: Date: 10/28/2021
C3.03

Texas Commission on Environmental Quality

TSS Removal Calculations 04-20-2009

Project Name: Jarrell ISD HS Additions
Date Prepared: 10/28/2021

1. The Required Load Reduction for the total project: Calculations from RG-348 Pages 3-27 to 3-30

Page 3-29 Equation 3.3: $L_{M,TOTAL PROJECT} = P \times (A_{I,PLAN} + A_{P,PLAN})$

where: $L_{M,TOTAL PROJECT}$ = Required TSS removal resulting from the proposed development = 80% of increased load
 $A_{I,PLAN}$ = Net increase in impervious area for the project
 P = Average annual precipitation, inches

Site Data: Determine Required Load Removal Based on the Entire Project
County = Williamson
Total project area included in plan = 119.54 acres
Predevelopment impervious area within the limits of the plan = 0.00 acres
Total post-development impervious area within the limits of the plan = 77.70 acres
Total post-development impervious cover fraction = 0.65
 P = 32 inches

$L_{M,TOTAL PROJECT} = 67631$ lbs.

Number of drainage basins / outfalls areas leaving the plan area = 1

2. Drainage Basin Parameters (This information should be provided for each basin):

Drainage Basin/Outfall Area No. = 1
Total drainage basin/outfall area = 119.54 acres
Predevelopment impervious area within drainage basin/outfall area = 0.00 acres
Post-development impervious area within drainage basin/outfall area = 77.70 acres
Post-development impervious fraction within drainage basin/outfall area = 0.65
 $L_{M,THIS BASIN} = 67631$ lbs.

3. Indicate the proposed BMP Code for this basin.

Proposed BMP = Wet Basin
Removal efficiency = 93 percent

4. Calculate Maximum TSS Load Removed (L_R) for this Drainage Basin by the selected BMP Type.

RG-348 Page 3-33 Equation 3.7: $L_R = (BMP \text{ efficiency}) \times P \times (A_I \times 34.6 + A_P \times 0.54)$

where: A_C = Total On-Site drainage area in the BMP catchment area
 A_I = Impervious area proposed in the BMP catchment area
 A_P = Pervious area remaining in the BMP catchment area
 L_R = TSS Load removed from this catchment area by the proposed BMP

$A_C = 119.54$ acres
 $A_I = 77.70$ acres
 $A_P = 41.84$ acres
 $L_R = 80681$ lbs

5. Calculate Fraction of Annual Runoff to Treat the drainage basin / outfall area

Desired $L_{M,THIS BASIN} = 67631$ lbs.

$F = 0.84$

6. Calculate Capture Volume required by the BMP Type for this drainage basin / outfall area.

Rainfall Depth = 1.26 inches
Post Development Runoff Coefficient = 0.46
On-site Water Quality Volume = 251249 cubic feet

Calculations from RG-348 Pages 3-36 to 3-37

Off-site area draining to BMP = 0.00 acres
Off-site Impervious cover draining to BMP = 0.00 acres
Impervious fraction of off-site area = 0
Off-site Runoff Coefficient = 0.00
Off-site Water Quality Volume = 0 cubic feet

Storage for Sediment = 50250
Total Capture Volume (required water quality volume(s) x 1.20) = 301499 cubic feet

11. Wet Basins

Designed as Required in RG-348 Pages 3-66 to 3-71

Required capacity of Permanent Pool = 301499 cubic feet
Required capacity at WQV Elevation = 552748 cubic feet
Permanent Pool Capacity is 1.20 times the WQV
Total Capacity should be the Permanent Pool Capacity plus a second WQV.


Forebay Volume					
Stage	Elevation	Contour Area	Incremental Storage	Total Storage	AC-FT
0.00	792.50	9,197	0	0	0.00
1.00	793.50	10,941	10,056	10,056	0.23
2.00	794.50	12,785	11,851	21,907	0.50
3.00	795.50	14,723	13,746	35,653	0.82
4.00	796.50	17,619	16,152	51,805	1.19
5.00	797.50	19,064	18,337	70,142	1.61

Wet Pond Volume					
Stage	Elevation	Contour Area	Incremental Storage	Total Storage	AC-FT
0.00	790.50	24,052	0	0	0.00
1.00	791.50	26,570	25,301	25,301	0.58
2.00	792.50	29,188	27,868	53,169	1.22
3.00	793.50	31,907	30,537	83,707	1.92
4.00	794.50	34,727	33,307	117,014	2.69
5.00	795.50	37,646	36,177	153,190	3.52
6.00	796.50	41,072	39,347	192,537	4.42
7.00	797.50	43,267	42,165	234,702	5.39


Detention Volume					
Stage	Elevation	Contour Area	Incremental Storage	Total Storage	AC-FT
0.00	797.50	71,870	0	0	0.0
0.50	798.00	115,911	46,509	46,509	1.1
1.00	798.50	158,337	68,287	114,796	2.6
1.50	799.00	203,725	90,277	205,073	4.7
2.00	799.50	252,950	113,947	319,020	7.3
2.50	800.00	306,244	139,586	458,607	10.5
3.00	800.50	350,982	164,179	622,786	14.3
3.50	801.00	372,774	180,912	803,698	18.5
4.00	801.50	390,874	190,894	994,592	22.8
4.50	802.00	405,993	199,205	1,193,797	27.4
5.00	802.50	410,995	204,246	1,398,042	32.1
5.50	803.00	416,023	206,753	1,604,796	36.8

	Discharge (CFS)		
	100-yr	10-yr	2-yr
Pre-project	729.6	395.6	207.5
Post-project (Detention)	704.9	374.4	200.8
Difference	-24.7	-21.2	-6.7
% Difference	-3.40%	-5.40%	-3.20%



	Pond Results		
	100-yr	10-yr	2-yr
Peak Storage (ac-ft)	26.7	20	15.2
Peak Elevation	801.9	801.2	800.6




- GENERAL SITE NOTES:
- CONTRACTOR TO ENSURE EDWARDS AQUIFER (EA) PERMITTING IS IN PLACE AND REVIEWED BEFORE BEGINNING ANY SITE DISTURBANCE.
 - ALL TEMPORARY EROSION CONTROLS SHALL BE INSTALLED PER EA REQUIREMENTS PRIOR TO ANY SITE DISTURBANCE.
 - CONTRACTOR SHALL REVIEW AND REFERENCE SITE GEOTECHNICAL REPORT PREPARED BY ALLIANCE ENGINEERING GROUP AND TITLED "SUBSURFACE EXPLORATION AND GEOTECHNICAL EVALUATION FOR JARRELL HIGH SCHOOL STORMWATER PROJECT, JARRELL, TEXAS" OR ANY ADDITIONS OR ADDENDUMS TO THE ORIGINAL REPORT.
 - CONTRACTOR SHALL PROPERLY DISPOSE OF ANY DEMOLISHED SITE FEATURES OR UTILITIES OFF-SITE. BURYING DEMOLISHED ELEMENTS WILL NOT BE ALLOWED.
 - CONTRACTOR SHALL WORK WITH PROJECT GEOTECHNICAL ENGINEER AND PROJECT CONSTRUCTION MATERIALS TESTING LAB TO IDENTIFY ON-SITE CLAY SOIL TO USE IN CREATING THE PERMANENT CLAY LINER FOR THE POND.
 - ON-SITE TOPSOIL IN THE AREA OF DISTURBANCE SHALL BE STRIPPED AND STOCKPILED FOR USE IN REVEGETATION OF DISTURBED AREAS. NO ADDITIONAL PAY ITEM WILL BE ALLOWED FOR TOPSOIL IMPORT. CONTRACTOR TO USE ON-SITE SOILS SUITABLE FOR HEALTHY REVEGETATION OF PROJECT.
 - ALL ON-SITE FILL AREAS SHALL BE STRIPPED, PROCESSED, AND COMPACTED UNDER THE DIRECTION OF THE PROJECT GEOTECH AND PROJECT CMT LAB. THE DISTRICT WILL USE UNKNOWN PORTIONS OF THE FILL AREAS AS FUTURE BUILDING EXPANSIONS. THEREFORE, CONTRACTOR WILL NEED TO PLACE ALL FILL IN A CONTROLLED MANNER AS DIRECTED BY THE PROJECT GEOTECH AND THE PROJECT CMT LAB.
 - CONTRACTOR TO WORK CLOSELY WITH THE PROJECT GEOTECHNICAL ENGINEERING/MATERIAL TESTING FIRM TO ENSURE MATERIAL USED TO CONSTRUCT ANY FEATURE USED TO IMPOUND WATER WILL REMAIN WATER TIGHT AND RESISTANT TO SOIL PIPING THROUGH THE FEATURE'S LIFE SPAN.
 - ALL CONDUITS ENTERING THE WATER IMPOUNDMENT STRUCTURE (WATER QUALITY POND) SHALL INCLUDE CLAY DAMS TO ENSURE THERE IS NO SOIL PIPING TO OR FROM THE CONDUIT EMBEDMENT MATERIAL.



GRAPHIC SCALE



KEY MAP
N.T.S.



Know what's below.
Call before you dig.

THESE PLANS ARE SUBJECT TO REVIEW & APPROVAL BY JURISDICTIONAL ENTITIES.

**** NOTICE TO CONTRACTORS - TOPOGRAPHIC SURVEY ****

TOPOGRAPHIC INFORMATION TAKEN FROM A TOPOGRAPHIC SURVEY PERFORMED BY 4WARD LAND SURVEYING. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. THE ENGINEER AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY ENGINEER AND OWNER.

Project: ATHLETICS COMPLEX IMPROVEMENTS AT JARRELL HIGH SCHOOL FOR JARRELL I.S.D. 1100 FM 487, JARRELL, TEXAS 76537

LANGAN | Adams

This drawing was prepared by LANGAN | Adams as an independent professional engineering service. It is not to be used for any other project or purpose without the express written consent of Langan | Adams. Langan | Adams is not responsible for any errors or omissions in this drawing, including but not limited to, the accuracy of the information, the quality of the work, or the results of the work.



TBPE Registration #: P-13,709

Huckabee

AUSTIN • DALLAS • FORT WORTH HOUSTON • SAN ANTONIO • WACO www.huckabee-inc.com 800.687.0228



WATER QUALITY & DETENTION POND GRADING, AND DEMOLITION PLAN

PACKAGE 1 1

Job No. 1835-06-01 Sheet No.


Drawn By: Date: 10/28/2021

C3.04



NOTE - WATER OF THE U.S. THERE ARE NO IMPACTS FROM CONSTRUCTION ACTIVITIES TO THE WATERS OF THE U.S. ON THIS SITE.

LEGEND	
INLET PROTECTION	IP - IP
LIMITS OF DISTURBANCE	—▲—
SILT FENCE	SF
CONSTRUCTION EXIT	
ROCK CHECK DAM	
PROPOSED FLOW ARROW	



KEY MAP N.T.S.

EROSION CONTROL NOTES

- CONTRACTOR MUST COMPLETE A CONSTRUCTION SITE NOTICE, OBTAIN SIGNED COPIES OF NOI FORM FOR BOTH OWNER AND CONTRACTOR (IF APPLICABLE TO THIS SITE), AND POST THEM AT THE CONSTRUCTION SITE, IN ACCORDANCE WITH THE NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM (NPDES) GENERAL PERMIT FOR CONSTRUCTION ACTIVITIES (TXR15000). THE GENERAL CONTRACTOR, (AND ALL SUBCONTRACTORS INVOLVED WITH ANY CONSTRUCTION ACTIVITY RELATED TO EARTHWORK, EROSION CONTROL, ETC., OR WHICH UTILIZE POSSIBLE POLLUTANTS AS DEFINED IN THE TPDES GENERAL PERMIT) MUST BE FAMILIAR WITH THE CONTENTS OF THE STORM WATER POLLUTION PREVENTION PLAN (SWPPP) AS WELL AS ALL THE REQUIREMENTS SET FORTH IN THE TPDES GENERAL PERMIT AND ANY APPLICABLE LOCAL PERMIT REQUIREMENTS, AND SHALL COMPLY WITH ALL SUCH REQUIREMENTS DURING ALL CONSTRUCTION ACTIVITIES.
- THE CONTRACTOR SHALL ADHERE TO THE SEQUENCE OF OPERATIONS FOR EROSION CONTROL IMPLEMENTATION SHOWN HEREON. ANY DEVIATION FROM THIS SEQUENCE DEEMED NECESSARY BY THE CONTRACTOR MAY REQUIRE THAT THE STORMWATER POLLUTION PREVENTION PLAN BE MODIFIED IN ACCORDANCE WITH THE NPDES GENERAL PERMIT GUIDELINES AND SECTION 1.01 F OF THE STORM WATER POLLUTION PREVENTION PLAN.
- THE CONTRACTOR SHALL MODIFY THIS PLAN TO SHOW LOCATIONS OF TEMPORARY WASHDOWN AREAS, PORTABLE TOILETS, EQUIPMENT MAINTENANCE/REPAIR AREAS, STOCKPILE AREAS, FUEL STORAGE AREAS, CONCRETE WASH-OUT PITS, AND POLLUTANT CONTROLS FOR EACH, AS SOON AS POSSIBLE. THE GENERAL PERMIT AUTHORIZES THE LAND DISPOSAL OF WASH OUT WATER FROM CONCRETE TRUCKS THAT ARE ASSOCIATED WITH OFF-SITE PRODUCTION FACILITIES, AS LONG AS THE DISCHARGE IS INTO SPECIFICALLY DESIGNATED DIKED AREAS WHICH HAVE BEEN PREPARED TO PREVENT CONTACT BETWEEN THE CONCRETE AND/OR WASH OUT WATER AND STORMWATER WHICH WILL BE DISCHARGED FROM THE SITE. TO PREVENT DIRECT DISCHARGE TO SURFACE WATERS (SEE CONCRETE WASHOUT DETAIL SHOWN IN PLANS). DIRECT DISCHARGE OF CONCRETE TRUCK WASH OUT WATER TO SURFACE WATERS IN THE STATE, INCLUDING DISCHARGE TO STORM SEWERS, IS PROHIBITED BY THE GENERAL PERMIT. IF A CONCRETE PLANT IS LOCATED AT CONSTRUCTION SITE, CONTRACTOR SHALL OBTAIN COVERAGE UNDER AND COMPLY WITH GENERAL PERMIT TXR110000 OR INDIVIDUAL PERMIT.
- THE GENERAL CONTRACTOR SHALL PERFORM ALL REQUIRED INSPECTIONS OF STORMWATER CONTROLS AND PRACTICES AT FREQUENCIES GIVEN IN THE NPDES GENERAL PERMIT, AND SHALL COMPLETE AND SIGN APPROPRIATE INSPECTION FORMS (AS PROVIDED IN THE SWPPP).
- OIL AND GREASE ABSORBING MATERIALS SHALL BE READILY AVAILABLE ON-SITE AND SHALL BE PROMPTLY USED TO CONTAIN AND/OR CLEAN UP ALL FUEL OR CHEMICAL SPILLS OR LEAKS.
- DUST CONTROL SHALL BE ACCOMPLISHED BY WATERING DRY, EXPOSED AREAS ON A REGULAR BASIS. SPRAYING OF PETROLEUM BASED OR TOXIC LIQUIDS FOR THIS PURPOSE IS PROHIBITED.
- DISTURBED AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE CEASED FOR AT LEAST FOURTEEN DAYS SHALL BE TEMPORARILY STABILIZED WITH VEGETATION AND MULCH.
- DISTURBED AREAS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE PERMANENTLY CEASED SHALL BE PERMANENTLY SEEDED WITHIN FOURTEEN DAYS PER SEEDING OR LANDSCAPING SPECIFICATIONS.
- ALL VEHICLES SHALL BE CLEANED AT THE CONSTRUCTION EXIT POINTS ACCORDING TO NOTES SHOWN ON THE DETAIL THEREOF. IF THE MAJORITY OF MUD OR DIRT IS NOT REMOVED FROM EXITING TRAFFIC, HOSE BIBS SHALL BE PROVIDED AT CONSTRUCTION TRAFFIC EXIT POINTS, AND VEHICLE TIRES SHALL BE WASHED BEFORE EXITING ONTO PUBLIC ROADS. SILT FROM THIS WASHING OPERATION SHALL BE INTERCEPTED AND TRAPPED BEFORE WASHWATER IS ALLOWED TO BE DISCHARGED OFF-SITE.
- ALL MATERIALS SPILLED, DROPPED, WASHED OR TRACKED ONTO ADJACENT ROADWAYS BY VEHICLES EXITING THE SITE SHALL BE CLEANED OR REMOVED IMMEDIATELY.
- CONTRACTOR SHALL PREVENT ANY SILTATION FROM ENTERING THE STORM SEWER SYSTEM. ALL INLETS AND INLET OPENINGS SHALL BE FULLY ENCLOSED WITH APPROPRIATE INLET PROTECTION DEVICES.
- THE CONTRACTOR SHALL REMOVE ALL ACCUMULATED SILT IN ANY TEMPORARY OR PERMANENT DETENTION PONDS, STORM SEWER INLETS AND PIPES, AND ALONG SILT FENCES, WITHIN 48 HOURS AFTER INSPECTION OF DEVICES REVEALS THE PRESENCE OF EXCESSIVE SILTATION (AS SPECIFIED IN SECTION 5.02 OF THE SWPPP).
- SILT FENCES SHALL BE PLACED AROUND ANY STOCKPILES USED ON THIS SITE.
- THE CONTRACTOR IS ADVISED TO CONSTRUCT TEMPORARY OR PERMANENT FENCING AROUND DETENTION PONDS AND SEDIMENT BASINS AT THE EARLIEST POSSIBLE TIME TO PREVENT ACCIDENTAL ACCESS BY PERSONS OR ANIMALS.
- ANY ADDITIONAL EROSION CONTROL MEASURES REQUIRED TO ENSURE COMPLIANCE WITH THE TPDES GENERAL PERMIT OR LOCAL PERMIT REQUIREMENTS SHALL BE IMPLEMENTED BY THE CONTRACTOR, AT NO ADDITIONAL EXPENSE TO THE OWNER.
- ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED AND PROPERLY DISPOSED OF OFF-SITE WITHIN THIRTY DAYS AFTER STABILIZATION OF ALL SURFACES.
- THE CONTRACTOR SHALL ASSUME LIABILITY FOR DAMAGE TO ADJACENT PROPERTIES AND/OR PUBLIC RIGHT-OF-WAY RESULTING FROM FAILURE TO FULLY IMPLEMENT AND EXECUTE ALL EROSION CONTROL PROCEDURES SHOWN AND NOTED IN THESE PLANS.
- WHENEVER DIRT, ROCK, OR OTHER MATERIALS ARE IMPORTED OR EXPORTED ON THE PRIMARY CONSTRUCTION SITE, CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR COMPLIANCE WITH ALL TCEQ STORMWATER REQUIREMENTS FOR THE REMOTE SITE. CONTRACTOR SHALL FURNISH THE ENGINEER AND THE OWNERS CONSTRUCTION MANAGER WITH DOCUMENTATION OF COVERAGE FOR THE BORROW OR FILL SITE UNDER A NPDES PERMIT FOR STORMWATER DISCHARGES AND OF A WRITTEN AGREEMENT WITH THE LANDOWNER OF THE REMOTE SITE INDICATING EROSION CONTROL MEASURES HAVE BEEN IMPLEMENTED THEREON. AT A MINIMUM, EROSION CONTROL MEASURES MUST CONSIST OF PERIMETER CONTROLS (SILT FENCES) ON ALL DOWN SLOPES AND SIDE SLOPE BOUNDARIES IF ANY DISTURBED AREA. REIS PROVISIONS FOR RE-VEGETATION AFTER THE FILL MATERIALS ARE IN PLACE.
- ALL SLOPES ON SITE WHICH ARE 1:1 OR STEEPER SHALL BE STABILIZED BY TRACK WALKING OR HANDERS UP AND DOWN THE SLOPE WITH A TRACKED VEHICLE) FOLLOWED BY INSTALLATION OF EROSION CONTROL BLANKET INSTALLED IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS. EROSION CONTROL BLANKET SHALL BE NORTH AMERICAN GREEN S150 OR APPROVED EQUAL.

EROSION CONTROL MAINTENANCE NOTES

- ALL MEASURES STATED ON THIS EROSION AND SEDIMENT CONTROL PLAN, AND IN THE STORM WATER POLLUTION PREVENTION PLAN, SHALL BE MAINTAINED IN FULLY FUNCTIONAL CONDITION UNTIL NO LONGER REQUIRED FOR A COMPLETED PHASE OF WORK OR FINAL STABILIZATION OF THE SITE. ALL EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE CHECKED BY A QUALIFIED PERSON ON A SCHEDULE WHICH COMPLIES WITH THE GENERAL PERMIT REQUIREMENTS AND CLEANED AND REPAIRED WITHIN 48 HOURS OF THE INSPECTION IN ACCORDANCE WITH THE FOLLOWINGS:
 - INLET PROTECTION DEVICES AND BARRIERS SHALL BE REPAIRED OR REPLACED IF THEY SHOW SIGNS OF UNDERMINING, OR DETERIORATION.
 - ALL SEEDED AREAS SHALL BE CHECKED REGULARLY TO SEE THAT A GOOD STAND IS MAINTAINED. AREAS SHOULD BE FERTILIZED, WATERED AND RESEED AS NEEDED.
 - SILT FENCES SHALL BE REPAIRED TO THEIR ORIGINAL CONDITIONS IF DAMAGED. SEDIMENT SHALL BE REMOVED FROM THE SILT FENCES WHEN IT REACHES ONE-HALF THE HEIGHT OF THE SILT FENCE.
 - THE TEMPORARY PARKING AND STORAGE AREA (IF PRESENT) SHALL BE KEPT IN GOOD CONDITION (SUITABLE FOR PARKING AND STORAGE). THIS MAY REQUIRE PERIODIC TOP DRESSING OF THE TEMPORARY PARKING AS CONDITIONS DEMAND.
 - OUTLET STRUCTURES IN THE SEDIMENTATION BASINS OR SEDIMENT TRAPS (IF PRESENT) SHALL BE MAINTAINED IN OPERATIONAL CONDITION AT ALL TIMES. SEDIMENT SHALL BE REMOVED FROM SEDIMENT BASINS OR TRAPS WHEN THE DESIGN CAPACITY HAS BEEN REDUCED BY 50%.
- MAINTENANCE PROCEDURES FOR THE EROSION AND SEDIMENTATION CONTROL SYSTEMS SPECIFIED ARE GIVEN IN SECTION 5 OF THE STORM WATER POLLUTION PREVENTION PLAN.

EROSION CONTROL SEQUENCE

- INSTALL SILT FENCES AROUND PERIMETER OF PROPERTY AND DISTURBED AREAS AS SHOWN.
- INSTALL ROCK CHECK DAMS AT THE ENDS OF ALL EXPOSED STORM SEWER PIPES, IF PRESENT.
- CONSTRUCT TEMPORARY CONSTRUCTION EXIT.
- COMMENCE GRUBBING AND REMOVAL OF VEGETATION IN AREA TO RECEIVE CUT OR FILL.
- COMMENCE GRADING OPERATION.
- INSTALL ALL PROPOSED STORM SEWER PIPES AND INSTALL INLET PROTECTION SILT FENCES AT ENDS OF EXPOSED PIPES.
- COMPLETE PLANTING AND/OR SEEDING OF VEGETATED AREAS TO ACCOMPLISH STABILIZATION, IN ACCORDANCE WITH THE LANDSCAPING PLAN.
- REMOVE TEMPORARY CONSTRUCTION EXIT, SILT FENCES & ROCK CHECK DAMS.

NOTE FOR CHANGES TO SWPPP

THE TXR15000 GENERAL PERMIT REQUIRES THAT THE PERMITTEE REVISE OR UPDATE THIS SWPPP WHENEVER THERE IS A CHANGE IN DESIGN, CONSTRUCTION, OPERATION, OR MAINTENANCE, OR WHENEVER THE RESULT OF AN INSPECTION INDICATES THAT THIS SWPPP IS INEFFECTIVE IN ELIMINATING OR SIGNIFICANTLY MINIMIZING POLLUTANTS IN STORMWATER DISCHARGES. HOWEVER, THE REGULATIONS OF THE TEXAS BOARD OF PROFESSIONAL ENGINEERS REQUIRE THAT CHANGES MADE BY THE CONTRACTOR DURING CONSTRUCTION MUST BE AUTHORIZED BY A LICENSED TEXAS ENGINEER. THESE CHANGES MAY BE AUTHORIZED BY THE ENGINEER OF RECORD THROUGH UPDATED DRAWINGS, WORK ORDER CHANGES, OR OTHER METHODS ACCEPTABLE TO THE ENGINEER, OR BY ANOTHER ENGINEER PROVIDED THAT THEY NOTIFY THE ENGINEER OF RECORD.

NOTE - STABILIZATION

ALL DISTURBED AREAS SHALL BE WATERED, FERTILIZED, AND SEEDED OR SOODED AS NECESSARY AND BY DEFINITION 'MAINTAINED' UNTIL AN ESTABLISHED STAND OF GRASS CAN BE RELEASED TO THE OWNER. REFERENCE LANDSCAPE/IRRIGATION PLAN (IF PROVIDED) TO COORDINATE PLANTING ENHANCEMENTS AND LIMITS OF IRRIGATION COVERAGE.

NOTE - MATERIAL STORAGE

THE CONTRACTOR SHALL NOTE ON SITE PLAN THE LOCATION OF ALL MATERIAL STORAGE AREAS, EQUIPMENT STORAGE AREAS, SOLID WASTE RECEPTACLES, SANITARY FACILITIES, ANY ON-SITE OR OFF-SITE BORROW OR STOCKPILE AREA, ANY ON-SITE OR OFF-SITE SUPPORT ACTIVITIES (SUCH AS ASPHALT OR CONCRETE PLANTS). CONTRACTOR SHALL ALSO PREPARE, KEEP ON SITE, AND MAINTAIN CURRENT A LIST OF MATERIALS WITH APPROXIMATE QUANTITIES, WHICH ARE STORED ON SITE.

** NOTICE TO CONTRACTORS - TOPOGRAPHIC SURVEY **

TOPOGRAPHIC INFORMATION TAKEN FROM A TOPOGRAPHIC SURVEY PERFORMED BY AWARD LAND SURVEYING. THE CONTRACTOR SHALL NOTIFY THE ENGINEER IMMEDIATELY, IN WRITING, OF ANY DISCREPANCIES OR OMISSIONS TO THE TOPOGRAPHIC INFORMATION. THE CONTRACTOR(S) SHALL BE RESPONSIBLE FOR CONFIRMING THE LOCATION (HORIZONTAL/VERTICAL) OF ANY BURIED CABLES, CONDUITS, PIPES, AND STRUCTURES (STORM SEWER, SANITARY SEWER, WATER, GAS, TELEVISION, TELEPHONE, ETC.) WHICH IMPACT THE CONSTRUCTION SITE. THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY DISCREPANCIES ARE FOUND BETWEEN THE ACTUAL CONDITIONS VERSUS THE DATA CONTAINED IN THE CONSTRUCTION PLANS. ANY COSTS INCURRED AS THE RESULT OF NOT CONFIRMING THE ACTUAL LOCATION (HORIZONTAL/VERTICAL) OF SAID CABLES, CONDUITS, PIPES, AND STRUCTURES SHALL BE BORNE BY THE CONTRACTOR. ADDITIONALLY, THE CONTRACTOR(S) SHALL NOTIFY THE OWNER AND ENGINEER IF ANY ERRORS OR DISCREPANCIES ARE FOUND ON THE CONSTRUCTION DOCUMENTS (PS&E), WHICH NEGATIVELY IMPACT THE PROJECT. THE ENGINEER AND OWNER SHALL BE INDEMNIFIED OF PROBLEMS AND/OR COST WHICH MAY RESULT FROM CONTRACTOR'S FAILURE TO NOTIFY ENGINEER AND OWNER.



Know what's below. Call before you dig.


THESE PLANS ARE SUBJECT TO REVIEW & APPROVAL BY JURISDICTIONAL ENTITIES.

Date

Revision /

ATHLETICS COMPLEX IMPROVEMENTS
AT JARRELL HIGH SCHOOL
FOR
JARRELL I.S.D.
1100 FM 487, JARRELL, TEXAS 76337

LANGAN | Adams



TBPE Registration # P-13,709

Huckabee



AUSTIN • DALLAS • FORT WORTH
HOUSTON • SAN ANTONIO • WACO
www.huckabee-rc.com
800.680.0228

WATER QUALITY & DETENTION POND SWPPP


PACKAGE 1 1

Job No. 1835-06-01 Sheet No. ---

Drawn By: --- Date: 10/28/2021 C3.05



B-B' (OUTLET) PROFILE




A-A' (POND) PROFILE

Revision / Date

ATHLETICS COMPLEX IMPROVEMENTS
 AT JARRELL HIGH SCHOOL
 FOR
 JARRELL I.S.D.
 1100 FM 487, JARRELL, TEXAS 76537

LANGAN | Adams



Huckabee
 AUSTIN • DALLAS • FORT WORTH
 HOUSTON • SAN ANTONIO • WACO
 www.huckabee-inc.com
 800.687.0228

WATER QUALITY & DETENTION POND PROFILE VIEWS

PACKAGE 1	1
Job No. 1836-06-01	Sheet No.
Drawn By:	C3.06
Date: 10/28/2021	

9/14/2021 1:57:27 PM
 C:\Users\jgallardo\Documents\2018 Revit Local Files\1836-06-01_JarrellISD_HS-AthleticsComplex_ARCH_V19_Jarrell.rvt

Date / Revision /

ATHLETICS COMPLEX IMPROVEMENTS
AT JARRELL HIGH SCHOOL
FOR
JARRELL I.S.D.
1100 FM 487, JARRELL, TEXAS 76537

LANGAN | Adams


This drawing was prepared by LANGAN | Adams as an instrument of service, and shall remain the property of Langan | Adams. The information herein shall be used only for the project for which it was prepared and shall not be used for any other project without the written consent of Langan | Adams. The engineer shall not be responsible for any errors or omissions in this drawing, including but not limited to, the omission of information, or any other information, which may be necessary for the proper construction and installation of the project. The engineer shall not be responsible for any errors or omissions in this drawing, including but not limited to, the omission of information, or any other information, which may be necessary for the proper construction and installation of the project.

JACK H. GARNER, P.E.
96447
10-28-2021
TBPB Registration #: P-13,709


Huckabee
AUSTIN • DALLAS • FORT WORTH
HOUSTON • SAN ANTONIO • WACO
www.huckabee-inc.com
800.687.0228

WATER QUALITY & DETENTION POND DETAILS


PACKAGE 1 1
Job No. 1836-06-01 Sheet No.
Drawn By: Date: 10/28/2021
C3.07





12' X 12' CONCRETE MAINTENANCE PAD
N.T.S.



DATE
MAY 1, 1997




ROCK ACCESS DRIVE
N.T.S.



9/14/2021 1:57:27 PM
C:\temp\2021\20210914\20210914-01_Jarrell.ISD_HS_AthleticsComplex_ARCH_V19_Jarrell.dwg

TYPICAL WET POND SPACING



- A SPIKERUSH (SHORT) PLANT 3-6 FEET ON CENTER
B WATER CLOVER
C BIG MUHLY
D BUR HEAD
E CARDINAL FLOWER
F ARROWHEAD PLANT 3 FEET ON CENTER
G PICKEREL WEED
H SPIKERUSH (TALL)
I AMERICAN WATER WILLOW
J COONTAIL
K POND WEED
L WATER NAIAD


Table 1-96 Pond Edge Zone Plants. Table 1-97 Marsh Zone Plants. Table 1-98 Deep Water Zone Plants. Columns include Common Name, Latin Name, Height, Required, and Comments and Planting Information.

NOTE: ALL WETLAND PLANTS WHICH FULFILL THE MINIMUM LANDSCAPE REQUIREMENTS SHALL BE PROPAGATED OR HARVESTED FROM THE REGIONALLY ADAPTED STOCK (WHEN POSSIBLE). THESE ARE PLANT SPECIES OR GENOTYPES WHICH ARE NATIVE TO A RANGE OF WITHIN 250 MILES OF THE PROJECT SITE.

WET POND J PLANTING PLAN. Surface Area of Permanent Pool = 1.03 ACRES. 44834/2 x 0.03 = 672 number of plants required (minimum)

Tables showing plant list edge zone, marsh zone, and deep water zone. Columns include Plant List Edge Zone, Ratio, Minimum No. of Plants, Provided No. of Plants, and Minimum Size.

NOTE: WET POND TO HAVE 12" TOPSOIL AND 24" CLAY LINER



1 CROSS SECTION OF A TYPICAL VEGETATED BENCH AREA

STANDARD NOTES

- IMPERMEABLE LINER MUST BE CLAY. CLAY LINERS SHALL MEET THE FOLLOWING SPECIFICATIONS:
1. SELECTION OF FILL MATERIAL SHOULD BE GUIDED BY THE FOLLOWING CRITERIA:
A. MINIMUM PLASTICITY INDEX: >30
B. MINIMUM LIQUID LIMIT: >50
C. MINIMUM SURFACE #200 SIEVE: >60%
D. NO STONES LARGER THAN 1"
E. FREE OF ORGANIC MATERIAL AND DEBRIS, SUCH AS LIMBS, BARKS, LEAVES, ETC.
2. COMPACTED SOIL SHOULD BE 95 PERCENT OF MAXIMUM LABORATORY DENSITY DETERMINED IN ACCORDANCE WITH AMERICAN SOCIETY OF TESTING MATERIALS, METHOD ASTM D 698, USING A COMPACTIVE EFFORT OF 7.16 FT.LBS./CU.IN.
3. PLACEMENT SHOULD BE IN LIFTS NOT EXCEEDING EIGHT INCHES AFTER COMPACTION, EACH COMPACTED LIFT SHOULD BE INSPECTED AND TESTED FOR DENSITY COMPLIANCE BY THE GEOTECHNICAL ENGINEER PRIOR TO PLACING THE NEXT LIFT...
4. TESTING AND QUALIFICATION OF RAW FILL MATERIAL, PLACEMENT, AND COMPACTION SHALL BE PERFORMED BY THE GEOTECHNICAL ENGINEER...
5. DEVIATIONS FROM THE ABOVE CRITERIA MAY BE PERMITTED ONLY UPON APPROVAL OF THE GEOTECHNICAL ENGINEER ON AN INDIVIDUAL BASIS.
GENERAL:
1. MICROBIAL INITIATION - A SUBSTANTIAL PORTION OF THE POLLUTANT REMOVAL IN WET PONDS IS DUE TO BIOLOGICAL PROCESSES...
2. INTEGRATED PEST MANAGEMENT - AS WITH ANY LANDSCAPE, THERE IS A NEEDS FOR PEST MANAGEMENT IN WET PONDS...
3. WATER - AFTER THE POND LINER IS COMPLETED, THE BASIN MUST FILL UP WITH WATER WITHIN A REASONABLE TIME PERIOD...
4. SOIL LINER MATERIAL MINIMUM PHYSICAL REQUIREMENTS REPRESENTATIVE SAMPLES OF THE SOILS TO BE USED FOR LINERS MUST FIRST BE TESTED...
5. MAKE-UP WATER - A NEARBY SOURCE FOR MAKE-UP (SUPPLEMENTAL) WATER IS RECOMMENDED AS A WAY TO MAINTAIN AN ADEQUATE PERMANENT POOL LEVEL...

- 2.3.2 CONSTRUCTED SOIL LINERS
THESE CONSTRUCTED SOIL LINERS INCLUDE THOSE OF OVER-EXCAVATED AND RECOMPACTED IN SITU SOILS AND SOILS FROM A BORROW SOURCE...
CLOD AND ROCK SIZE
THE MAXIMUM CLOD SIZE OF THE COMPACTED LINER SOILS SHALL BE APPROXIMATELY ONE INCH IN DIAMETER BUT IN ALL CASES SOIL CLODS SHALL BE REDUCED TO THE SMALLEST SIZE NECESSARY TO ACHIEVE THE COEFFICIENT OF PERMEABILITY REPORTED BY THE TESTING LABORATORY...
16 COMPACTIVE EFFORT (SOILS COMPACTION)
ALL CONSTRUCTED SOIL LINERS MUST BE COMPACTED WITH A PAD/TAMPING-FOOT (PREFERABLE) OR PRONGFOOT ROLLER (\$830.205(G), MSWR)...


- 18 QUALITY ASSURANCE AND TESTING FREQUENCY FOR SOIL LINERS
EACH IN SITU OR CONSTRUCTED LINER SIDEWALL AND FLOOR AREA DEVELOPED AS A SEPARATE SEGMENT (NON-MONOLITHICALLY) MUST BE CONSIDERED AS SEPARATELY EVALUATED AREAS INDEPENDENT OF EACH OTHER FOR THE PURPOSE OF CALCULATING DIMENSIONS TO DETERMINE THE REQUIRED NUMBER OF SAMPLES...
1. PAD/TAMPING-FOOT ROLLERS, OR
2. PRONG-FOOT (SHEEPSFOOT) ROLLERS
THE FOLLOWING EQUIPMENT TYPES ARE EXAMPLES OF THAT WHICH IS NOT PERMITTED OR APPROPRIATE FOR THE COMPACTION OF SOIL LINERS:
1. BULLDOZER
2. RUBBER-TIRED (PNEUMATIC) ROLLERS
3. FLAT-WHEELED ROLLERS
4. RUBBER-TIRED SCRAPERS OR BELLY DUMPS

Date:
Revision /

ATHLETICS COMPLEX IMPROVEMENTS
AT JARRELL HIGH SCHOOL
FOR
JARRELL I.S.D.
1100 FM 487, JARRELL, TEXAS 76337

Project:

LANGAN | Adams



TBPE Registration #1-F-13,709

Huckabee
Austin • Dallas • Fort Worth
Houston • San Antonio • San Diego
www.huckabee-inc.com
800.687.0228

WATER QUALITY & DETENTION POND NOTES

Table with columns: PACKAGE 1, 1; Job No. 1835-06-01; Sheet No. C3.08; Date: 10/28/2021.